

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-40427-00-00  
Spot: W2W2SE Sec/Twnshp/Rge: 31-24S-4E  
1320 feet from S Section Line, 2970 feet from W Section Line  
Lease Name: MAXWELL Well #: 1  
County: BUTLER Total Vertical Depth: 2701 feet

Operator License No.: 5387  
Op Name: THE BUCKEYE CORPORATION DBA A  
Address: PO BOX 1020  
EL DORADO, KS 67042

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD   | 5.5  | 2672       |             | 12 SX    |
| SURF   | 7    | 2446       |             | 35 SX    |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/07/2013 12:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: STEVEN W. KILE Company: \_\_\_\_\_ Phone: (316) 321-6690

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: PATRICK SHIELDS WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/11/2013 12:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

Perfs:

6/7/13 PHILLIPS RIH W/TBG TO 2690'. CONSOLIDATED SPOT A 70 SX CMT PLUG.  
LET SET 1 HR AND TAGGED CMT @ 2236'. 6/10/13 DYNALOG SHOT  
PERFORATIONS @ 250'. RIH S/A PKR IN 60' AND SET. PUMP 326 SKS OF CMT  
DOWN 5 1/2" CSG AND AROUND AND BETWEEN THE 5 1/2" AND 7" CASINGS.  
FILLED THE CELLAR W/CMT. SDON. 6/11/13 CMT 8' FROM SURFACE. FILLED UP  
AND RIGGED DOWN.

Remarks: CONSOLIDATED

Plugged through: CSG


KCC WICHITA

JAN 31 2014

RECEIVED

District: 02

Signed



02/07/14

(TECHNICIAN)