

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-40428-00-00
Spot: S2SW Sec/Twnshp/Rge: 31-24S-4E
660 feet from S Section Line, 1320 feet from W Section Line
Lease Name: MAXWELL 'A' Well #: 1
County: BUTLER Total Vertical Depth: 2680 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION DBA A
Address: PO BOX 1020
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	12.5	56		
PROD	8.625	1950		
PROD	5.5	2680		0 SX
SURF	0	0		0 SX
SURF	8.125	315		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/03/2013 12:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: STEVEN W. KILE Company: _____ Phone: (316) 322-5776

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: PATRICK SHIELDS WitnessType: PARTIAL
Date/Time Plugging Completed: 06/06/2013 12:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report: _____ Perfs: _____

6-3-13 PHILLIPS RAN TBG INTO 2660'. CONSOLIDATED SPOT 50 SKS CMT. WAITED 1 HR AND TAGGED CMT @ 2528'. SDON. 6-5-13 DYNOLG SHOT 5 1/2" CSG OFF @ 350". PULLED CSG OUT OF THE HOLE. SDON. RIH W/7" PKR ON 3 JTS OF TBG. SET PKR AND CIRCULATED CMT TO SURFACE DOWN THE 7" AND AROUND THE BACKSIDE TO SURFACE. PULLED PKR OUT OF THE HOLE, FILLED 7" TO TOP W/CMT. SDON. 6-6-13 TAGGED CMT @ 109' IN THE CSG AND 20' ON THE BACKSIDE. FILLED THE CSG W/CMT AND RAN 1" ON THE BACKSIDE AND FILLED TO SURFACE W/CMT.

Remarks: CONSOLIDATED
Plugged through: CSG

KCC WICHITA
JAN 31 2014
RECEIVED

District: 02

Signed [Signature]
07/07/14 (TECHNICIAN)