

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-19580-00-00  
Spot: SWNENWSW Sec/Twnshp/Rge: 36-33S-14E  
2211 feet from S Section Line, 4462 feet from E Section Line  
Lease Name: LUCKYBECK Well #: 3  
County: MONTGOMERY Total Vertical Depth: 650 feet

Operator License No.: 34526  
Op Name: THE RAVEN COMPANY LLC  
Address: PO BOX 6691  
GRANBURY, TX 76049

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	625		0 SX
SURF	12	20		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/20/2013 12:00 AM  
Plug Co. License No.: 31696 Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: RON CUNNINGHAM Company: \_\_\_\_\_ Phone: (620) 330-2724

Proposed Plugging Method: Run 1" to bottom, gel hole, put a 50' cement plug at bottom, pull 1" to 225', cement to surface, pull 1" out, top off cement.  
run 1" to 225' on backside, cement to surface, pull 1" out, top off cement.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/21/2013 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to TD gelled hole and spotted 25 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped inside of casing off. (35 sacks). Washed 1" to 225' on backside of production casing and circulated cement to surface. Pulled 1" and topped well off. (34 sacks). A total of 94 sacks of cement were used to plug this well.

Perfs:

RECEIVED  
JAN 28 2014  
KCC Cherokee Dist. #3  
DS

Remarks: WELL WAS PLUGGED DUE TO COMPLAINT AND WOULD NOT MEET TA STATUS.

Plugged through: TBG

District: 03

Signed [Signature]  
02/07/14 (TECHNICIAN)

KCC WICHITA  
JAN 31 2014  
RECEIVED  
Form CP-2/3