

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-25076-00-00  
Spot: SEENWSE Sec/Twnshp/Rge: 35-33S-14E  
2258 feet from S Section Line, 1545 feet from E Section Line  
Lease Name: WEST LUCKYBECK Well #: J-106  
County: MONTGOMERY Total Vertical Depth: 669 feet

Operator License No.: 34526  
Op Name: THE RAVEN COMPANY LLC  
Address: PO BOX 6691  
GRANBURY, TX 76049

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	669		0 SX
SURF	8.625	50		0 SX

Well Type: EOR UIC Docket No: E13823.35 Date/Time to Plug: 01/24/2014 12:00 AM  
Plug Co. License No.: 31696 Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: RON CUNNINGHAM Company: Phone: (620) 289-4700

Proposed Plugging Method: Run 1" to bottom, gel hole, spot a 50' plug of cement on perfs, pull up to 225', circulate cement to surface, pull pipe out, top off cement.

Plugging Proposal Received By: LARRY MARCHANT WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/24/2014 3:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Pulled and fished 2" out of well to 525'. Ran 1" to 525' and circulated cement to surface. Pulled 1" and topped well off. A total of 33 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
614	637		
RECEIVED JAN 28 2014 KCC Chanute Dist. #3 DS			

Remarks: WELL PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

District: 03

Signed [Signature]  
cc to WCC 01/30/14  
01/27/14 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

JAN 31 2014

RECEIVED