

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22469-00-00  
Spot: S2N2NW Sec/Twnshp/Rge: 36-6S-20W  
4290 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: WILLS Well #: 6  
County: ROOKS Total Vertical Depth: 3665 feet

Operator License No.: 5399  
Op Name: TREK AEC, LLC  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3664		150 SX
SURF	8.625	328		180 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/10/2014 11:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: THAD STARR Company: TREK AEC, LLC Phone: (620) 793-2146

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
DV Tool at 1490' w/250 sx cwc  
Production perforation: 3622' - 3632'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/10/2014 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Tubing stuck. Casing leak. Pulled rods and pump out. Cut tubing off at 3140'. Pulled and tested. Ran back tubing to 3140'. Global pumped 100 sx cement w/200 # hulls. Pulled tubing to 1750' and pumped 150 sx cement w/300 # hulls. Cement circulated. PTOH. Topped off 4 1/2" casing with 20 sx cement. Casing full.

Perfs:

Top	Bot	Thru	Comments
3622	3632		
3552	3553		
3531	3532		
3517	3518		

Remarks: GLOBAL

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

01/07/14

CM

JAN 14 2014

KCC WICHITA

Form CP-2/3

JAN 22 2014

RECEIVED