

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22061-00-00
Spot: NENESW Sec/Twnshp/Rge: 20-24S-5E
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BLUESTEM Well #: 1-B
County: BUTLER Total Vertical Depth: 2656 feet

Operator License No.: 33971
Op Name: TRIPower RESOURCES, LLC
Address: BOX 849
ARDMORE, OK 73402

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2631		200 SX
SURF	8.625	205		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/25/2013 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GARY L. REED Company: _____ Phone: (316) 733-4798

Proposed Plugging Method: Set bridge plug @ 2515'. Dump bail 2sx cement on top of bridge plug. Fill casing with fluid. Perforate 4.5" casing @ 255'. Circulate cement from 255' to surface in annulus. Leave casing full of cement from 255' to surface.

Plugging Proposal Received By: PATRICK SHIELDS WitnessType: PARTIAL
Date/Time Plugging Completed: 11/25/2013 12:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

SET CIBP @ 2518' KB. DUMP BAILED 2 SX CLASS A CEMENT ON TOP OF BRIDGE PLUG. PERFORATED 4.5" CASING @ 268' KB. CIRCULATED TO SURFACE FROM 268' WITH 92 SX 60/40 POZ +4% GEL +2% CACL. LEFT 4.5" FULL OF CEMENT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2565	2570		

Remarks:

Plugged through: CSG

District: 02

Signed



01/02/14 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

JAN 31 2014

RECEIVED

130