

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21859-00-00
Spot: S2N2SESE Sec/Twnshp/Rge: 7-32S-13W
785 feet from S Section Line, 660 feet from E Section Line
Lease Name: BROOK Well #: 1-7
County: BARBER Total Vertical Depth: 4496 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4050		WITH 2 SX CMT
CIBP		4300		
COND	16	45		WITH 10 SX CMT
PROD	4.5	4493	2500	WITH 175 SX CMT
SURF	8.625	436		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/16/2014 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 4050'. PLUG AT 700' WITH 10-15 SX GEL & 50 SX CMT. PLUG AT 470' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL SELLERS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/16/2014 10:15 AM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

PLUGGING ORDERS DIFFERENT DUE TO OVER PUMPING FIRST PLUG. CIBP @ 4050' WITH 2 SX CMT. 1ST PLUG AT 720' WITH 100 SX CMT. 2ND PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4371	4378		
4100	4102		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

RECEIVED
JAN 28 2014
KCC DODGE CITY

Signed

Daniel Sellers
02/03/14
(TECHNICIAN)
KCC WICHITA

FEB 03 2014

RECEIVED

Form CP-2/3