

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-22878-00-00  
Spot: SENENWSE Sec/Twnshp/Rge: 16-20S-23W  
2008 feet from S Section Line, 1624 feet from E Section Line  
Lease Name: MAUCH Well #: 1-16  
County: NESS Total Vertical Depth: 4450 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1395		CEMENTED TO SURFACE
PROD	5.5	4450	0	WITH 125 SX CMT
SURF	8.625	598		WITH 325 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/31/2013 3:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOE RUPP Company: VESS OIL Phone: (785) 798-5151

Proposed Plugging Method: SQUEEZE WITH 25 SX CMT & 150# HULLS. PLUG AT 1560' CIRCULATE CMT TO SURFACE. CHECK BACKSIDE WITH CMT TO 500#.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/03/2014 12:30 PM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

PLUGGED PERFS WITH 25 SX CMT & 200# HULLS. PLUG AT 1560' WITH 215 SX CMT. CMT DID NOT CIRCULATE TO SURFACE. WILL TAG CMT. 1/3/14: WENT IN WITH TBG & FOUND CMT AT 750'. PUMPED 75 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 5 SX CMT. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4390	4396		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED

JAN 13 2014

KCC DODGE CITY

Signed

*Daniel Sellers*  
01/03/14

(TECHNICIAN)

KCC WICHITA

Form CP-2/3

JAN 16 2014

RECEIVED

*Raw*