

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22896-00-00
Spot: SWNESE Sec/Twnshp/Rge: 16-20S-23W
1988 feet from S Section Line, 643 feet from E Section Line
Lease Name: MAUCH Well #: 2-16
County: NESS Total Vertical Depth: 4505 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4350		WITH 2 SX CMT
DVT	5.5	1406		CEMENTED TO SURFACE
PROD	5.5	4489	0	WITH 125 SX CMT
SURF	8.625	642		WITH 325 SX CMT

Well Type: SWD UIC Docket No: D24287.0 Date/Time to Plug: 01/03/2014 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE RUPP Company: VESS OIL Phone: (785) 798-5151

Proposed Plugging Method: SET CIBP @ 4439' WITH 2 SX CMT. PLUG AT 1560' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE WITH CMT TO 500#.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/03/2014 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4350' & SPOT 2 SX CMT. RAN TBG TO 1560' & PUMPED 155 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 5 SX CMT. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4489	4505		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED

JAN 13 2014

KCC DODGE CITY

Signed

Michael Maier
ce to mc 01/20/14
02/07/14

TECHNICIAN KCC WICHITA

JAN 16 2014

Form CP-2/3

RECEIVED

ADY