

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19681-00-00

Spot: SWNESE

Sec/Twnshp/Rge: 5-26S-4E

1650 feet from S Section Line, 990 feet from E Section Line

Lease Name: RICE A

Well #: 3

County: BUTLER

Total Vertical Depth: 2541 feet

Operator License No.: 5030

Op Name: VESS OIL CORPORATION

Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2484		
PROD	5.5	2540	50	SX
SURF	8.25	100	0	SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/03/2014 12:00 AM

Plug Co. License No.: 32991

Plug Co. Name: SIMMONS WELL SERVICE, INC.

Proposal Rcvd. from: CASEY COATS

Company:

Phone: (316) 655-1997

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: PATRICK SHIELDS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/03/2014 12:00 AM

KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

RUN TUBING TO 2470'. CONSOLIDATED MIXED AND PUMPED 35 SX CLASS A, 4 % CC. 1/4# SX POLY FLAKES. TRIP OUT. WIRELINE TAG CEMENT @ 2169'. KCC PATRICK SHIELDS ON SITE. PERF 4 SHOTS AT 250', TIGHT, CAN'T CIRCULATE; PERF @ 4 SHOTS @ 225'; TIGHT, CAN'T CIRCULATE. PERF 4 SHOTS @ 170': GOOD CIRCULATION OUTSIDE OF 7" MIX AND PUMP 220 SX 60/40 POZMIX, 4% GEL, 1% CC. GOOD CEMENT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2486	2488		
2478	2481		

Remarks: CONSOLIDATED TICKET #43200.

Plugged through: TBG

District: 02

Signed



02/07/14 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

JAN 31 2014

RECEIVED