

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21729-00-00
Spot: NWSENWNW Sec/Twnshp/Rge: 19-33S-19W
811 feet from N Section Line, 711 feet from W Section Line
Lease Name: BAKER FARMS 3319 Well #: 2-19
County: COMANCHE Total Vertical Depth: 6318 feet

Operator License No.: 34192

Op Name: SANDRIDGE EXPLORATION AND PRO.
Address: 123 ROBERT S. KERR AVE DUCTION,
OKLAHOMA CITY, OK 73102 LLC

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4680		WITH 5 SX CMT
CIBP		5200		
COND	20	120		WITH 10 SX CMT
PROD	5.5	6313	1987	WITH 395 SX CMT
SURF	8.625	500		WITH 400 SX CMT

Well Type: SIGW UIC Docket No: _____ Date/Time to Plug: 12/26/2013 2:00 PM
Plug Co. License No.: 34982 Plug Co. Name: TITAN WELL SERVICE, LLC
Proposal Rcvd. from: ANTHONY Company: TITAN WELL SERVICE, LLC Phone: (405) 828-4225

Proposed Plugging Method: CIBP @ 4680'. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/27/2013 4:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

CIBP @ 4680' WITH 5 SX CMT. CIRCULATED HOLE WITH MUD. 1ST PLUG AT 1000' WITH 50 SX CMT. 2ND PLUG AT 530' WITH 50 SX CMT. 3RD PLUG AT 32' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5252	5258		
5236	5239		
4732	4736		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
JAN - 8 2014
KCC DODGE CITY

Signed

Nathan Willis
RECEIVED
KANSAS CORPORATION COMMISSION (TECHNICIAN)
JAN 13 2014
CONSERVATION DIVISION
WICHITA, KS