

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-24049-00-00
Spot: SENWSESE Sec/Twnshp/Rge: 14-31S-15W
741 feet from S Section Line, 843 feet from E Section Line
Lease Name: BEAR CREEK RANCH 3115 Well #: 1-14
County: BARBER Total Vertical Depth: 4917 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4082		WITH 5 SX CMT
CIBP		4215		
PROD	5.5	4914	0	WITH 240 SX CMT
SURF	8.625	498		WITH 300 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/27/2013 3:00 PM
Plug Co. License No.: 34979 Plug Co. Name: L.C.B. RESOURCES, LLC
Proposal Rcvd. from: OLIVER ROZELL Company: SANDRIDGE EXPLORATION & PR Phone: (405) 429-5500

Proposed Plugging Method: CIBP @ 4075' WITH 2 SX CMT. PERFORATE @ 700' & CIRCULATE WITH CMT & 10 SX GEL OR PLUG AT 700' WITH 10 SX GEL & 40 SX CMT. PLUG AT 520' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/31/2013 8:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

12/27/13: CIBP @ 4082' WITH 5 SX CMT. PRESSURE TESTED TO 1000 PSI & HELD. PERFORATE @ 700'. ATTEMPTED TO CIRCULATE WITH WATER. NO RETURNS. SHUT DOWN. 12/28/13: SHOT CASING OFF AT 750' & LAID DOWN CASING. SHUT DOWN. 12/30/13: RUN 2 7/8" TBG IN TO 714'. 1ST PLUG AT 714' WITH 40 SX CMT. LET CMT SET. TAG TOC @ 557'. 2ND PLUG AT 520' WITH 50 SX CMT. NO RETURNS. LET CMT SET. RUN TBG BACK IN TO 520'. DIDN'T FIND TOP OF CMT. PUMPED ANOTHER 50 SX CMT AT 520'. BROKE CIRCULATION. 3RD PLUG AT 60' WITH 20 SX CMT. LAY DOWN TBG. TOP OFF WITH 10 SX CMT. HOLE ON SLIGHT VACUUM. 12/31/13: RUN TBG IN & TAG TOC @ 242'. CIRCULATE CMT TO SURFACE WITH 65 SX CMT. LAID TBG DOWN & TOP OFF HOLE WITH 2 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4222	4228		
4160	4170		
4125	4130		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION
JAN 13 2014
CONSERVATION DIVISION
WICHITA, KS

RECEIVED

JAN - 8 2014

KCC DODGE CITY