

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20828-00-01
Spot: SESWSESE Sec/Twnshp/Rge: 26-26S-24W
320 feet from S Section Line, 730 feet from E Section Line
Lease Name: BROBEE 2624 Well #: 1-26
County: FORD Total Vertical Depth: 6630 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4660		WITH 2 SX CMT
CIBP		4990		
CIBP		5540		
CIBP		5750		
COND	20	130		WITH 13 YDS CMT
PROD	7	5845	0	WITH 280 SX CMT
SURF	9.625	1449		WITH 510 SX CMT

Well Type: SLOW UIC Docket No: _____ Date/Time to Plug: 12/05/2013 2:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE JOHNSON Company: SANDRIDGE EXPLORATION Phone: (405) 397-1986

Proposed Plugging Method: SET CIBP @ 4660' WITH 2 SX CMT. PLUG AT 1600' WITH 75 SX CMT. PLUG AT 950' WITH 75 SX CMT. PLUG AT 60' WITH 25 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/15/2014 10:50 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

BRIDGE PLUGS SET AT 4990' & 5750'. SET CIBP @ 4660' WITH 2 SX CMT. OPERATOR TRIED TO RECOVER 1518' OF 7" CASING BUT FOUND OUT THAT THE 7" HAD BEEN CEMENTED TO SURFACE. 1ST PLUG AT 1615' WITH 50 SX CMT. 2ND PLUG AT 945' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 25 SX CMT. PRESSURED ANNULUS TO 500#. WILL DRILL OUT & BOND LOG. NO CMT IN 9 5/8". 1/14/14: DRILLED OUT THE TOP PLUG & RAN A CBL FROM THE TOP OF THE 945' PLUG. NO CMT WAS FOUND BEHIND THE 7". DRILLED OUT THE 945' PLUG & RAN A CBL FROM THE TOP OF THE 1615' PLUG. FOUND TOC @ 1310'. PERFORATED AT 950'. 1/15/14: RAN TBG TO 1500' & PUMPED 30 SX CMT. PULLED TBG OUT OF THE HOLE. TIED ONTO THE 7" & CIRCULATED CMT INSIDE & OUTSIDE THE 7" WITH 270 SX CMT FROM 950' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5554	5646		
5012	5174		
4717	4867		

KCC WICHITA

JAN 22 2014

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED

District: 01

JAN 17 2014

Signed

[Signature]
02/07/14

(TECHNICIAN)

KCC DODGE CITY