

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21568-00-00
Spot: SWSWSESW Sec/Twnshp/Rge: 31-30S-23W
185 feet from S Section Line, 1412 feet from W Section Line
Lease Name: CARROLL 3023 Well #: 1-31
County: CLARK Total Vertical Depth: 5657 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	60		
SURF	9.625	1220		WITH 690 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/07/2014 8:00 PM
Plug Co. License No.: 34127 Plug Co. Name: TOMCAT DRILLING LLC
Proposal Rcvd. from: DAVID MEZO Company: SANDRIDGE EXPLORATION & PR Phone: (405) 429-5500

Proposed Plugging Method: 1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 1250' WITH 75 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/08/2014 12:30 AM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

Perfs:

CIRCULATED HOLE WITH MUD @ 1535'. 1ST PLUG AT 1535' WITH 50 SX CMT. 2ND PLUG AT 1258' WITH 75 SX CMT. 3RD PLUG AT 597' WITH 50 SX CMT. 4TH PLUG AT 62' WITH 30 SX CMT. 5TH PLUG CIRCULATED RAT HOLE WITH 30 SX CMT. 6TH PLUG CIRCULATED MOUSE HOLE WITH 20 SX CMT. GOOD RETURNS DURING PUMPING.

Remarks: USED 60/40 POZMIX 4% GEL BY OTEX.

Plugged through: DP

District: 01

Signed

Nathan Willis
02/07/14
(TECHNICIAN)

RECEIVED

JAN 10 2014

KCC DODGE CITY

KCC WICHITA

Form CP-2/3

JAN 16 2014

RECEIVED