

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-191-22693-00-00
 Spot: SWNE Sec/Twnshp/Rge: 33-32S-4W
1980 feet from N Section Line, 1980 feet from E Section Line
 Lease Name: JESSE 3204 Well #: 1-33
 County: SUMNER Total Vertical Depth: 4800 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4510		
PROD	5.5	4795		800 SX
SURF	8.625	355		250 SX
TI	2.875	4619		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/06/2013 12:00 AM
 Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
 Proposal Rcvd. from: ALAN TIEDEMAN Company: _____ Phone: (405) 429-5500

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: HUNTER CLARK WitnessType: NONE
 Date/Time Plugging Completed: 12/06/2013 12:00 AM KCC Agent: JEFF KLOCK

Actual Plugging Report:

12/6/13 TO 12/7/13 - RIH AND SET CIBP @ 4136', DUMPED 5 SKS OF CEMENT ON TOP OF PLUG AND RD EWL. RIH WITH 125 JOINTS OF 2 7/8" TUBING DISPLACED WELL WITH 9PPG DRILLING MUD AND TESTED TO 1000 PSI. POOH LAYING DOWN TUBING TO 800' FROM SURFACE AND SPOTTED 10 SKS OF CEMENT FOR PLUG. POOH STANDING BACK, RU EWL AND RIH WITH PERFORATING GUN AND SHOT SQUEEZE HOLES @ 400' FROM SURFACE. RIH TO 400', COULD NOT ESTABLISH INJECTION RATE AND THE KCC DECIDED TO CIRCULATE CEMENT BACK TO SURFACE INSIDE THE 5 1/2" CASING. RDMO WOR AND SDFN. 12/7/13 MIRU WELDER, DUG DOWN TO 6' AND CUTOFF WELL HEAD AND CASING AT 4' BELOW GROUND LEVEL AND WELDED ON ID CAP. BACK FILLED PIT AND AROUND WELL HEAD.

Perfs:

Top	Bot	Thru	Comments
4548	4558		
4174	4190		

KCC WICHITA
 FEB 05 2014
 RECEIVED

Remarks: ALLIED OIL & GAS SERVICES TICKET #062407

Plugged through:

District: 02

Signed Jeff Klock
02/07/14 (TECHNICIAN)