

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-24119-00-00
Spot: S2S2S2SE Sec/Twnshp/Rge: 34-30S-14W
165 feet from S Section Line, 1320 feet from E Section Line
Lease Name: LAMBERT 3014 Well #: 1-34
County: BARBER Total Vertical Depth: 4638 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	9.625	1034		WITH 450 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/21/2014 9:00 AM
Plug Co. License No.: 34870 Plug Co. Name: O-TEX PUMPING, LLC
Proposal Revd. from: DEVON MESO Company: SANDRIDGE Phone: (405) 429-5500

Proposed Plugging Method: 1ST PLUG AT 1070' WITH 75 SX CMT. 2ND PLUG AT 360' WITH 75 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: NONE
Date/Time Plugging Completed: 01/21/2014 11:00 AM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

1ST PLUG AT 1025' WITH 75 SX CMT. 2ND PLUG AT 350' WITH 75 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY O-TEX.

Plugged through: DP

District: 01

Signed Nathan Willis
02/07/14 (TECHNICIAN)

RECEIVED

JAN 27 2014

KCC DODGE CITY

KCC WICHITA

FEB 03 2014

RECEIVED

Form CP-2/3