

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-22232-00-00
Spot: NWSESESW Sec/Twnshp/Rge: 35-22S-31W
335 feet from S Section Line, 2305 feet from W Section Line
Lease Name: SCHMITT 2231 Well #: 1-35
County: FINNEY Total Vertical Depth: 5214 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4800		WITH 5 SX CMT
PROD	5.5	5214	0	WITH 590 SX CMT
SURF	8.625	1845		WITH 625 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/15/2014 3:00 PM
Plug Co. License No.: 34982 Plug Co. Name: TITAN WELL SERVICE, LLC
Proposal Rcvd. from: ANTHONY Company: TITAN WELL SERVICE, LLC Phone: (405) 828-4225

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/16/2014 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1/15/14: CIBP @ 4800' WITH 5 SX CMT. CIRCULATED HOLE WITH MUD. 1/16/14: 1ST PLUG AT 2000' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 40 SX CMT. TOOH W/TBG. PERFORATE @ 350'. ESTABLISH INJECTION RATE 2 BPM @ 600#. CIRCULATE CMT TO SURFACE THROUGH PERFORATIONS USING 80 SX CMT. 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4853	4860		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
02/07/14

(TECHNICIAN)

KCC WICHITA

JAN 27 2014

RECEIVED

RECEIVED

JAN 23 2014

KCC DODGE CITY

Form CP-2/3

AK