

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-24050-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 13-31S-15W
2154 feet from S Section Line, 2096 feet from E Section Line
Lease Name: THOMPSON 3115 Well #: 1-13
County: BARBER Total Vertical Depth: 5018 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4020		WITH 5 SX CMT
CIBP		4476		
CIBP		4540		
COND	20	40		WITH 10 SX CMT
PROD	5.5	5015	0	WITH 255 SX CMT
SURF	8.625	496		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/27/2013 8:30 AM
Plug Co. License No.: 34979 Plug Co. Name: L.C.B. RESOURCES, LLC
Proposal Rcvd. from: OLIVER ROZELL Company: SANDRIDGE EXPLORATION & PR Phone: (405) 429-5500

Proposed Plugging Method: CIBP @ 4020' WITH 5 SX CMT. PERFORATE @ 700' & CIRCULATE CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2013 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

CIBP @ 4020' WITH 5 SX CMT. PRESSURE TESTED TO 1000 PSI & HELD. CIRCULATED HOLE WITH MUD. PERFORATE @ 700' & PUMPED 380 SX CMT. CMT DID NOT CIRCULATE. DISPLACED HOLE WITH 15 BBL WATER. GOT A LITTLE LESS THAN 1/2 RETURNS WHILE PUMPING. WILL RUN BOND LOG. 12/28/13: RUN TBG IN 5 1/2" CASING & FOUND TOC @ 685'. RUN CMT BOND LOG & FOUND TOC IN 5 1/2" X 8 5/8" ANNULUS AT 150'. 12/30/13: PERFORATE 5 1/2" CASING AT 100'. RUN TBG IN 5 1/2" CASING TO 684'. 1ST PLUG AT 684' WITH 15 SX CMT. 2ND PLUG AT 400' WITH 15 SX CMT. 3RD PLUG AT 100' TO SURFACE WITH 10 SX CMT. 4TH PLUG PUMPED DOWN 5 1/2" CASING CIRCULATING CMT TO SURFACE (30 SX CMT) UP 5 1/2" X 8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4560	4572		
4505	4514		
4168	4174		
4070	4074		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

RECEIVED

JAN - 8 2014

KCC DODGE CITY

Signed

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 13 2014

CONSERVATION DIVISION
WICHITA, KS