

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21795-00-00
Spot: NWSESENW Sec/Twnshp/Rge: 23-20S-11W
3020 feet from S Section Line, 3059 feet from E Section Line
Lease Name: REISER A Well #: 1
County: BARTON Total Vertical Depth: 3285 feet

Operator License No.: 9292
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL
Address: 211 S FRONT ST
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3281		100 SX
SURF	8.625	223		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/23/2013 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: TIM SCHECK Company: SCHECK OIL Phone: (785) 483-4096

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement and 12 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/23/2013 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 490' and 200'.
Ran tubing to 3100' and pumped 12 sx gel followed by 50 sx cement. Pulled tubing to 1400' and pumped 90 sx cement. Pulled tubing to 490'. Circulated cement to surface on casing and surface pipe w/150 sx cement. Pulled tubing and topped off w/5 sx cement.
GPS: 38.29813 -098.50854

Perfs:

Remarks: COPELAND ACID AND CEMENTING
Plugged through: CSG

District: 04

Signed Bruce Rodie
02/07/14 (TECHNICIAN) CM
KCC WICHITA

DEC 27 2013

JAN 28 2014

RECEIVED