

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21761-00-00
Spot: NWSESESW Sec/Twnshp/Rge: 30-31S-7W
339 feet from S Section Line, 2080 feet from W Section Line
Lease Name: HOSTETLER 3107 Well #: 30-1
County: HARPER Total Vertical Depth: 5836 feet

Operator License No.: 34574
Op Name: SHELL GULF OF MEXICO INC.
Address: 150 N DAIRY-ASHFORD (77079) PO BO
HOUSTON, TX 77001

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	18	60		8 SX
PKR		4904		
PROD	7	4965		CMT W/619 SXS
SURF	9.625	750		500 SX
T1	4.5	4906		

Well Type: SWD UIC Docket No: D30996.0 Date/Time to Plug: 05/28/2013 12:00 AM
Plug Co. License No.: 34906 Plug Co. Name: TEXAS CES, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: KEN SCOFIELD Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/27/2013 12:00 AM KCC Agent: JEFF KLOCK

Actual Plugging Report:

Perfs:

CIBP SET AT 4,924 IN 7" CASING AT TOP OF ARBUCKLE. TOP WITH 250 SKS CLASS H. TAGED AT 4674'. FILL HOLE WITH 9.5 LB/GAL WBM TO 112' MD. SET CIBP IN 7" CASING AT 110' -112' MD BELOW THE LOWEST WATER IN THE COUNTY. CEMENT TO 6' BELOW GROUND LEVEL AND CAPPED WITH STEEL CAP. THE 7" CASING HAD BEEN CEMENTED TO SURFACE BY BAKER HUGHES ON JUNE 18, 2012. TICKET #1001916101.

KCC WICHITA
JAN 30 2014
RECEIVED

Remarks: BAKER HUGHES SERVICES, MCALESTER, OK CEMENTED THIS PLUG JOB. TICKET #1001990659

Plugged through: TBG

District: 02

Signed _____

Jeff Klock
(TECHNICIAN)
cc to UIC 2/07/14
2/07/14