

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21783-00-00

Spot: W2SWSWSE

Sec/Twnshp/Rge: 27-31S-6W

330 feet from S Section Line, 2332 feet from E Section Line

Lease Name: STUCHAL TRUST 3106

Well #: 27-1

County: HARPER

Total Vertical Depth: 60 feet

Operator License No.: 34574

Op Name: SHELL GULF OF MEXICO INC.

Address: 150 N DAIRY-ASHFORD (77079) PO BO
HOUSTON, TX 77001

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	18	60		36 SX
PROD	0	0		0 SX
SURF	0	0		0 SX

Well Type: SWD

UIC Docket No: D31063.0

Date/Time to Plug: 05/05/2013 12:00 AM

Plug Co. License No.: 5893

Plug Co. Name: PRATT WELL SERVICE, INC.

Proposal Rcvd. from: WILLARD LEVY

Company:

Phone: (620) 896-1412

Proposed Plugging Method: 1. Check Total Depth of conductor/mouse hole. (Document) 2. Check for static water level. (Document) 3. Cut conductor/mouse pipe off 5' below surface. 4. Set trim pipe to bottom of hole pump Type H cement until full. 5. Return next day check for settling top off if settled. 6. Weld cap on pipe and weep hole.

Plugging Proposal Received By:

Witness Type: NONE

Date/Time Plugging Completed: 05/06/2013 12:00 AM

KCC Agent: JEFF KLOCK

Actual Plugging Report:

Perfs:

1. DOCUMENTED TOTAL DEPTH OF CONDUCTOR AT 35' AND MOUSE HOLE AT 52'. 2. DOCUMENTED STATIC WATER LEVEL AT 12' FOR CONDUCTOR AND 15' FOR MOUSE HOLE. 3. CUT CONDUCTOR/MOUSE PIPE OFF 5' BELOW SURFACE. 4. PUMPED 35 SACKS FOR CONDUCTOR AND 25 SACKS FOR MOUSE HOLE OF TYPE H CEMENT UNTIL FULL. 5. RETURNED NEXT DAY, CHECKED FOR SETTLING, TOP OFF NOT NEEDED. 6. WELDED CAP ON PIPE AND WEEP HOLE.

KCC WICHITA
FEB 05 2014
RECEIVED

Remarks:

Plugged through:

District: 02

Signed

Jeff Klock
(TECHNICIAN)
cc to UIC 2/07/14