

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-30317-00-00
Spot: NENESE Sec/Twnshp/Rge: 4-28S-6E
2035 feet from S Section Line, 292 feet from E Section Line
Lease Name: LINDGREN Well #: 1
County: BUTLER Total Vertical Depth: 3074 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 NW 24TH ST.
OKLAHOMA CITY, OK 73105

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	308		
PROD	5.5	3073		175 SX
SURF	8.625	207		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2013 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: DALLAS FLOWERS, CROW Company: CROWN ENERGY CO Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND 50' ABOVE OH & CAP W/5 SXS CEMENT. PERF @ 260' & CIRC. 260' -0'. 60/40 POZMIX 4% GEL

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/15/2013 10:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2990', DUMP BAILED 5 SXS CEMENT ON TOP. TAGGED CEMENT @ 2950'. RIH ON WIRELINE SET CIBP @ 308'. PRESSURED CASING @ 100# HELD OK. RIH ON WIRELINE SHOT SQUEEZE HOLES 250' - 251' (4 HOLES). SWEDGED INTO 5.5 CSG, CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 100 SXS 60/40 POZMIX 3% CC, 4 % GEL. 1/4# POLYFLAKE TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10:30 AM 10-15-2013. CONSOLIDATED CEMENT TICKET #43676.

Perfs:

Top	Bot	Thru	Comments
3073	3074	OH	

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
02/10/14 (TECHNICIAN)

KCC WICHITA

JAN 29 2014

RECEIVED