

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20698-00-00
Spot: SESESE Sec/Twnshp/Rge: 4-28S-6E
363 feet from S Section Line, 333 feet from E Section Line
Lease Name: LINDGREN Well #: 3
County: BUTLER Total Vertical Depth: 3075 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 333 N PORTLAND AVE
OKLAHOMA CITY, OK 73107

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3073		
PROD	5.5	3073		75 SX
SURF	8.625	200		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2013 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND 50' ABOVE OH & CAP W/5 SXS CEMENT. PERF @ 260' & CIRC. 260'-0'.
60/40 POZMIX 4% GEL.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG CIRCULATING VARIOUS BRIDGES @ 608', 1118', & 3046'. CIRCULATED HOLE CLEAN @ 3069', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS 60/40 POZMIX 3% CC 4% GEL & 3/4 #POLYFLAKE & DISPLACED IN CASING, WAITED 2 HOURS, TAGGED CEMENT PLUG @ 2892'. RIH ON WIRELINE SHOT SQUEEZE HOLES FROM 250'-0'. SWEDGED INTO 5.5 CSG, CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 120 SXS 60/40 POZMIX 3% CC, 4% GEL, 1/4# POLYFLAKE, LOST CIRCULATION, PUMPED ANOTHER 170 SXS 60/40 POZMIX 3% CC, 4% GEL, 1/4# POLYFLAKE. (TOTAL OF 290 SXS) SDON. 10-11-2013, TAGGED CEMENT @ 652'. SWEDGED INTO 5.5 CSG CONSOLIDATED OIL WELL ESTABLISHED CIRCULATION, MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL 3% CC 1/4# POLYFLAKE TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 11:00 AM 10-11-2013. CONSOLIDATED CEMENT TICKET #43648, & 43649. 10-14-2014, TAGGED CEMENT @ 40', TOPPED WELL BACK TO SURFACE W/20 SXS. P & A COMPLETE.

Perfs:

Top	Bot	Thru	Comments
3073	3075	OH	

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
02/10/14 (TECHNICIAN)

KCC WICHITA Form CP-2/3

JAN 29 2014

RECEIVED