

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24490-00-00
Spot: S2SWNWSW Sec/Twnshp/Rge: 11-16S-14W
1550 feet from S Section Line, 4950 feet from E Section Line
Lease Name: KARST A Well #: 1
County: BARTON Total Vertical Depth: 3404 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3392	460	175 SX
SURF	8.625	455		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/09/2014 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1197

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls. Sanded off ar buckle open hole and topped with cement. Pulled stretch to cut casing and casing parted at 460'. Pulled 460' of casing.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/09/2014 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500' and 910'. Ran tubing to 1560' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 950' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 450'. Circulated cement to surface with 175 sx cement. Pulled tubing. Hole stayed full.
GPS: 38.67104 -098.84829

Perfs:

Top	Bot	Thru	Comments
3392	3404		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie
01/10/14 (TECHNICIAN) CM

JAN 14 2014

KCC WICHITA

Form CP-2/3

JAN 22 2014

RECEIVED