

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22099-00-00
Spot: SENENWNE Sec/Twnshp/Rge: 10-28S-8W
500 feet from N Section Line, 1625 feet from E Section Line
Lease Name: KLETKE Well #: 10-1
County: KINGMAN Total Vertical Depth: 2231 feet

Operator License No.: 31739
Op Name: IUKA-CARMI DEVELOPMENT LLC
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1866	1102	150 SX
SURF	8.625	282		220 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 12/12/2013 4:00 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GARELD INSLEE Company: _____ Phone: (620) 770-0995

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: HUNTER CLARK Witness Type: PARTIAL
Date/Time Plugging Completed: 12/12/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 1800' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 1102' PULLED CASING. RAN TUBING INTO 1060' SPOTTED 35 SX OF CEMENT. PULLED TUBING TO 764' SPOTTED 35 SX CEMENT. PULLED TUBING TO 344' CIRCULATED TO SURFACE WITH 120 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
1811	1812		

Remarks: QUALITY WELL SERVICE DID CEMENTING WITH, 60/40 4% POS MIX, TICKET #6059

Plugged through: TBG

District: 02

Signed

B. J. Hope
✓ *02/10/14*

(TECHNICIAN)

KCC WICHITA

JAN 29 2014

RECEIVED

Form CP-2/3

JK