

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23190-00-00
Spot: SWSWNWSW Sec/Twnshp/Rge: 18-23S-6E
1586 feet from S Section Line, 5067 feet from E Section Line
Lease Name: BREW-STEWART Well #: 5-18
County: BUTLER Total Vertical Depth: 1650 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1599	900	120 SX
SURF	8.625	216		105 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2013 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: SCOTT HAMPEL Company: _____ Phone: (316) 636-2737

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 09/12/2013 12:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

SANDED OFF BOTTOM TO 1520'. CUT SURFACE OFF 4' BELOW GROUND. BAILED 4 SACKS OF CEMENT ON SAND. RIPPED CASING AT 1030' AND 900'. PULLED CASING UP TO 270' AND SWEDGED IN. PUMPED 95 SACKS CEMENT AT 270 TO SURFACE. (ALL CEMENT WAS 60/40 POZMIX WITH 4% GEL)

Perfs:


Top	Bot	Thru	Comments
1573	1578		

Remarks:

Plugged through: CSG

District: 02

Signed


02/10/14 (TECHNICIAN)

KCC WICHITA Form CP-2/3

JAN 31 2014

RECEIVED

52