

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23155-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 24-23S-5E
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: STRAIT Well #: 6-24
County: BUTLER Total Vertical Depth: 1952 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1945	1003	120 SX
SURF	8.625	208		110 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2013 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: SCOTT HAMPEL Company: _____ Phone: (316) 636-2737

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 09/27/2013 12:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

SAND WAS AT 1530'. BAILED 4 SACKS CEMENT ON SAND. CUT SURFACE OFF 4' BELOW GROUND. RIPPED CASING AT 1003'. PULLED CASING UP TO 271' AND PUMPED 115 SACKS OF CEMENT TO SURFACE (4% GEL). PULLED REST OF CASING. TOPPED OFF WITH 5 SACKS CEMENT. (ALL CEMENT WAS 60/40 POZMIX WITH 4% GEL)

Perfs:


Top	Bot	Thru	Comments
1591	1596		

Remarks:

Plugged through: CSG

District: 02

Signed


02/10/14 (TECHNICIAN)

KCC WICHITA Form CP-2/3

JAN 31 2014

RECEIVED