

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-20017-00-01  
Spot: NWSW Sec/Twnshp/Rge: 2-30S-9W  
1980 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: WHITMER-SWINGLE Well #: 1  
County: KINGMAN Total Vertical Depth: 4267 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 4.5   | 4259       | 1850        | 150 SX   |
| SURF   | 8.625 | 237        |             | 200 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2013 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: \_\_\_\_\_

Proposed Plugging Method: SAND TO REC PIPE. 35 SX 1350', 35 SX 900', CIRC 300'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/30/2013 8:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

35 SX 150# HULLS AT 3850' ON BOTTOM. RECOVERED 1850' OF 4 1/2". PULLED 4 1/2" TO 1350' SPOTTED 35 SX CEMENT. PULLED TUBING TO 900' SPOTTED 35 SX CEMENT. PULLED TUBING TO 900' SPOTTED 35 SX CEMENT. PULLED TUBING TO 300' & CIRCULATED WITH 130 SX CEMENT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4220 | 4231 |      |          |

Remarks: QUALITY WELL SERVICE COMMON CEMENT

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

*[Handwritten Signature]*  
02/10/14 (TECHNICIAN)

KCC WICHITA

JAN 31 2014

RECEIVED