

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-01097-00-02
Spot: SENWNW Sec/Twnshp/Rge: 1-12S-23W
4295 feet from S Section Line, 4350 feet from E Section Line
Lease Name: NEWCOMER Well #: 1-2
County: TREGO Total Vertical Depth: 3954 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	0		bottom unknown
SURF	10.75	310		210 sx

Well Type: EOR UIC Docket No: E16356.2 Date/Time to Plug: 01/23/2014 11:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: TODD DINKEL Company: PROFESSIONAL PULLING SERVIC Phone: (785) 628-7443

Proposed Plugging Method: Ordered 600 sx 60/40 pozmix 4% gel cement w/900 # hulls and 24 sx gel. DV Tool at 1874' w/black magic.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2014 4:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3671' and pumped 24 sx gel followed by 100 sx cement w/200 # hulls. Pulled tubing to 1891' and pumped 225 sx cement w/200 # hulls. Good circulation of cement. Pulled tubing out. Topped off with 15 sx cement. Hole standing full. Backside full of black magic.
GPS: 39.04187 -099.83075

Perfs:

Remarks: ALLIED CEMENTING TICKET # 55020

Plugged through: TBG

KCC WICHITA
JAN 30 2014
RECEIVED

District: 04

Signed [Signature]
(TECHNICIAN)
cc to VMC 2/07/14
02/10/14 CM

JAN 24 2014