

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22413-00-01  
Spot: N2SWSWSW Sec/Twnshp/Rge: 12-7S-21W  
430 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: KEN HOLSMAN OWWO Well #: 1  
County: GRAHAM Total Vertical Depth: 3600 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3649		125 SX
SURF	8.625	216		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2013 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Production perforations at 3364' - 3368' and 3379' - 3435'. DV Tool at 1740' cwc

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/30/2013 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2950' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1920' and pumped 100 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing. Hooked to 4 1/2" casing and pumped 20 sx cement. Shut in pressure 400 psi. Hooked to 8 5/8" x 4 1/2" annulus and pumped 15 sx cement. Backside full of cement.

GPS: 39.45368N -099.61929W

Perfs:

Top	Bot	Thru	Comments
3379	3435		
3364	3368		

Remarks: ALLIED TICKET # 54738

Plugged through: TBG

District: 04

Signed Pat Bedore  
02/07/14 (TECHNICIAN) CM

NOV 06 2013

KCC WICHITA

Form CP-2/3

NOV 27 2013

RECEIVED