

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-059-24412-00-00  
Spot: SESESE Sec/Twnshp/Rge: 1-18S-20E  
310 feet from S Section Line, 329 feet from E Section Line  
Lease Name: HANSON Well #: E-2  
County: FRANKLIN Total Vertical Depth: 730 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	725		85 SX
SURF	7	20		0 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/25/2013 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: IF CAN PMP WTR INTO WELL/FM, PMP AND FILL PROD CSG W/CMT, PRESS UP ON SAME, AND SHUT WELL IN. IF CAN NOT PMP FLUID, RIH W/1TBG TO BTM, PMP AND FILL PROD CSG W/CMT, POOH 1"TBG, TOP WELL OFF W/CMT, PRESS UP ON SAME AND SHUT WELL IN. RETURN AT A LATER DATE, CUT CSG OFF BELOW "PLOW DEPT".

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE  
Date/Time Plugging Completed: 06/25/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO TD IN 2-7/8 INCH CASING AND FILL TO SURFACE WITH PORTLAND CEMENT. PULL OUT 1-INCH, TOP OFF, THEN SQUEEZE SHUTTING IN AT 750 PSI. USE TOTAL OF 28 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
523	538		

RECEIVED  
JAN 29 2014  
KCC Chanute Dist. #3  
LS

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]  
01/31/14 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

JAN 31 2014

RECEIVED