

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-059-25057-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 19-17S-21E
5229 feet from S Section Line, 4279 feet from E Section Line
Lease Name: LAGALLE Well #: 19-1
County: FRANKLIN Total Vertical Depth: 918 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	908		108 SX
SURF	8.625	51		48 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/01/2013 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO BTM, PMP PROD CSG FULL OF "GEL" THEN PMP A 50' CMT PLUG AT TD, PULL UP TBG TO 600', THEN PMP A 100' CMT PLUG, PULL UP TBG TO 250' AND FILL PROD CSG TO SURFACE W/CMT, POOH TBG, TOP PROD CSG OFF, PRESS UP ON SAME, AND SHUT WELL IN. RETURN AT A LATER DATE, CUT CSG OFF BELOW "PLOW DEPTH".

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed: 07/01/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

PUMP 2 SACKS OF GEL INTO CASING AT TD. PLACE 50 FOOT CEMENT PLUG AT TD, 50 FOOT PLUG AT 500 FEET, AND CEMENT FROM 250 FEET TO SURFACE. USE TOTAL OF 50 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
642	650		
610	650		

RECEIVED

JAN 29 2014

KCC Chanute Dist. #3


LS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

KCC WICHITA Form CP-2/3

JAN 31 2014

RECEIVED