

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-059-24854-00-00
Spot: NWNESE Sec/Twnshp/Rge: 30-17S-21E
2164 feet from S Section Line, 933 feet from E Section Line
Lease Name: SPENCER Well #: 3
County: FRANKLIN Total Vertical Depth: 656 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	645		0 SX
SURF	7	20		0 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/01/2013 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: IF CAN PMP WTR INTO WEL/FM, THEN PMP IN AND FILL THE PROD CSG W/CMT, PRESS UP ON SAME AND SHUT IN. IF CAN MOT PMP FLUID, RIH W/1"TBG TO BTM, PMP PROD CSG FULL OF CMT, POOH TBG, TOP PROD CSG OFF W/CMT, PRESS UP AND SHUT WELL IN. RETURN AT A LATER DATE, CUT CSG OFF "PLOW DEPTH".

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed: 07/01/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

PUMP 2 SACKS OF GEL INTO CASING AT TD. PLACE 50 FOOT CEMENT PLUG AT TD, 50 FOOT PLUG AT 500 FEET, AND CEMENT FROM 250 FEET TO SURFACE. USE TOTAL OF 49 SACKS OF CEMENT.

Perfs:

RECEIVED

JAN 29 2014

KCC Chanute Dist. #3

LS

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
07/01/14 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

JAN 31 2014

RECEIVED