

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-059-21799-00-00

Spot: SENWNWNW

Sec/Twnshp/Rge: 25-17S-20E

4834 feet from S Section Line, 4865 feet from E Section Line

Lease Name: WILLIAMS/SPENCER

Well #: 1

County: FRANKLIN

Total Vertical Depth: 751 feet

Operator License No.: 5150 •

Op Name: COLT ENERGY INC

Address: PO BOX 388
IOLA, KS 66749

| <u>String</u> | <u>Size</u> | <u>Depth (ft)</u> | <u>Pulled (ft)</u> | <u>Comment</u> |
|---------------|-------------|-------------------|--------------------|----------------|
| PROD | 2.875 | 690 | | 0 SX |
| SURF | 7 | 21 | | 0 SX |

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 06/27/2013 12:00 AM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Rcvd. from: COLT ENERGY, INC

Company:

Phone: (620) 365-3111

Proposed Plugging Method: IF CAN PMP WTR INTO WELL/FM, PUMP PROD CSG FULL OF CMT AND PRESS UP ON SAME, THEN SHUT WELL IN WITH PRESSURE. IF CANNOT PMP FLUID, THEN RIH W/1" TBG TO BTM, PMP AND FILL PROD CSG W/CMT, POOH TBG, TOP WELL OFF W/CMT, PRESS UP ON SAME, AND SHUT IN. RETURN LATER, CUT CSG OFF BELOW "FLOW DEPTH".

Plugging Proposal Received By: LEVI SHORT

WitnessType: NONE

Date/Time Plugging Completed: 06/27/2013 12:00 AM

KCC Agent: LEVI SHORT

Actual Plugging Report:

Perfs:

RUN 1-INCH TO TD IN 2-7/8 INCH CASING AND FILL TO SURFACE WITH PORTLAND CEMENT. PULL OUT 1-INCH, TOP OFF, THEN SQUEEZE SHUTTING IN AT 810 PSI. USE TOTAL OF 26 SACKS OF CEMENT.

RECEIVED

JAN 29 2014

KCC Chanute Dist. #3

LS

Remarks:

Plugged through: TBG

District: 03

Signed

LS
02/06/14

(TECHNICIAN)

KCC WICHITA

Form CP-2/3

JAN 31 2014

RECEIVED