

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-01128-00-00
Spot: NWNENWSE Sec/Twnshp/Rge: 22-25S-4E
2377 feet from S Section Line, 1676 feet from E Section Line
Lease Name: EATON A Well #: 3
County: BUTLER Total Vertical Depth: 2624 feet

Operator License No.: 31142
Op Name: PETROLEUM PROPERTY SERVICES, IN
Address: 125 N MARKET SUITE 1251
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6.625	2598		0 SX
SURF	15.5	155		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/05/2013 12:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: LEON KUHN Company: _____ Phone: (785) 483-1559

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: PATRICK SHIELDS WitnessType: PARTIAL
Date/Time Plugging Completed: 09/10/2013 12:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

Perfs:


RUN TUBING TO 2300'. DUMPED 50 SX CLASS A, 2% CC; PULL TUBING TAG PLUG AT 1650'. PERF 250-251, 4 SHOTS. PUMPED 300 SX 60/40 POZ, 4 % GEL, 2% CC. NO CEMENT TO SURFACE. RAN 7 JTS DOWN BACKSIDE OF CASING AND PUMPED 225 SX 60/40 POZ 4% GEL, 2% CC, NO CEMENT TO SURFACE. RAN 2 1/2 JTS DOWN BACKSIDE; PULL UP 1/2 JT AND PUMPED 70 SX 60/40 POZ, 4% GEL, 2% CC TO SURFACE. TOH W/TUBING. RAN 2 1/2 JTS TUBING IN CASING TAG ON 1/2 JT. PULLED 1/2 JT OUT. PUMPED 25 SX TO SURFACE & TOH W/TBG. PUMPED 43 SX DOWN BACKSIDE TO CAP OFF. CHECKED WELL NEXT A.M. DUMPED 50 SX CLASS A DOWN BACKSIDE OF CASING.

Remarks:

Plugged through: TBG

District: 02

Signed


02/11/14
(TECHNICIAN)

KCC WICHITA Form CP-2/3

JAN 31 2014

RECEIVED

✓ SK