

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-01142-00-00  
Spot: NESENE SW Sec/Twnshp/Rge: 22-25S-4E  
1701 feet from S Section Line, 2320 feet from W Section Line  
Lease Name: STARR A Well #: 2  
County: BUTLER Total Vertical Depth: 2612 feet

Operator License No.: 31142  
Op Name: PETROLEUM PROPERTY SERVICES, IN  
Address: 125 N MARKET SUITE 1251  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2592		0 SX
SURF	0	0		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/04/2013 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: LEON KUHN Company: \_\_\_\_\_ Phone: (785) 483-1559

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/05/2013 12:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

RUN TUBING DOWN TO 1207'. CONSOLIDATED SET 1ST PLUG WITH 50 SX CLASS 'A', 2% CC. RAN 8 JTS TUBING DOWN BACKSIDE. CONSOLIDATED PUMPED 215 SX CLASS A 2% NO RETURN, RAN BACK TO 1207' PUMP 50 SX CLASS A, 2% CC. CIRC CEMENT UP BACKSIDE. RAN SANDLINE. TAG CEMENT INSIDE AT 20' MIX & PUMP 30 SX CLASS A, 2% CC. TAG CEMENT ON BACKSIDE AT 90', MIX & PUMP 123 SX CLASS 'A'. 2% CC. CIRCULATE CEMENT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2595	2612		

Remarks: CONSOLIDATED

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

✓ 02/04/14

KCC WICHITA Form CP-2/3

JAN 31 2014

RECEIVED

1/31