

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-059-24852-00-00
Spot: NESESWE Sec/Twnshp/Rge: 31-17S-21E
482 feet from S Section Line, 1639 feet from E Section Line
Lease Name: MACDOUGAL " Well #: 4
County: FRANKLIN Total Vertical Depth: 700 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 2.875 | 691 | | 0 SX |
| SURF | 7 | 20 | | 0 SX |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/29/2013 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: IF CAN PMP WTR INTO WELL/FM, THEN PMP IN AND FILL PROD CSG W/CMT, PRESS UP ON SAME AND SHUT WELL IN. IF CAN NOT PMP FLUID, RIH W/1" TBG TO BTM, PMP AND FILL PROD CSG W/CMT, POOH 1" TBG, TOP OFF CSG W/CMT, PRESS UP ON SAME AND SHUT WELL IN. RETURN AT A LATER DATE AND CUT CSG OFF BELOW "PLOW DEPTH."

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE
Date/Time Plugging Completed: 05/29/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO TD IN 2-7/8 INCH CASING AND FILL TO SURFACE WITH PORTLAND CEMENT. PULL OUT 1-INCH, TOP OFF. USE TOTAL OF 28 SACKS OF CEMENT.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 608 | 618 | | |

RECEIVED
JAN 29 2014
KCC Chanute Dist. #3
LS

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

KCC WICHITA CP-2/3

JAN 31 2014

RECEIVED