

16 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 1963
5-6-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Jones & Gebert Oil Co.

Complete Address: ²⁰⁵
~~1007~~ Central Bldg., Wichita, Kansas

Lease Name McGrath Well No. # 1

Location C SE NW Sec. 16 Twp. 33 Rge. 14 (E) (W)W

County Barber Total Depth 4751

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Jones & Gebert Oil Co.

Address: 1007 Central Bldg., Wichita, Kansas License No.

Operation Completed: Hour 6:00PM Day 1st Month May Year 1963

The Above well was plugged as follows:

812' of 8 5/8" surface pipe, cement circulated with 400 sacks. Hole
was filled to 805' with mud and cemented with 25 sacks through the
drill pipe. Hole filled with mud to 450', 2nd cementing plug, 1/4 sack
hulls, cemented with 25 sacks. Hole was filled with mud to 40', 3rd
cementing plug, 1/4 sack hulls. cemented with 15 sacks to base cellar.
Rat hole and mouse hole, bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

5/6/63

INV. NO.

4014-W

Signed:

Archie Elving
Well Plugging Supervisor