

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1965
4-26-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Champlin Petroleum Company

Complete Address: P. O. Box 308, Ellinwood, Kansas

Lease Name Davis Ranch "C" Well No. # 1

Location C SW SE Sec. 21 Twp. 33 Rge. 14 (E) (W) W

County Barber Total Depth 4675'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 3:30PM Day 24th Month April Year 1965

The Above well was plugged as follows:

200' of 13 3/8" surface pipe, cement circulated. 4673' of 5 1/2" long
string, cemented with 125 sacks. Plug back to 4647'. Top perforation
4605'. Bottom of the hole was sanded to 4600', and cemented with 5
sacks. Pipe parted and 590' of 5 1/2" long string was recovered from the
hole. Hole was filled with mud to 225', and 10' of rock bridge, and
cemented with 35 sacks, bringing the top of the cement to 181' in the
surface pipe. Hole was filled with mud to 35', and 10' of rock bridge,
and cemented with 20 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/26/65
INV. NO. 1058-W

Signed: Archie Elving
Well Plugging Supervisor