

ej GP

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
10-12-71
OCT 12 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name R.W. Rine Drlg. Co.

Complete Address 600 R.H. Garvey Bldg. Wichita, Ks

Lease Name Anna M. Bowman Well No. 1

Location SW/NE/SE Sec. 23 Twp. 33 Rge. 14 (E) (W) W

County Barber Total Depth 4966

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering Co. Inc.

Address Box 698 Great Bend, Ks License No. 670

Operation Completed: Hour 5:00 PM Day 7 Month 10 Year 1971

The above well was plugged as follows:
273 ft 8 5/8 surface pipe cemented with 175 sacks. 4962 ft 5 1/2 long
string cemented with 250 sacks. Top perf. 4817 ft. Sand back to
4800 ft, 5 sacks cement with bailer. Pulled 3400 ft 5 1/2. Set 20 ft
rock bridge at 260 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: A. Russell Bihunter
Well Plugging Supervisor

INVOICED

DATE 10-12-71
INV. NO. 4444-W