

~~KANSAS~~

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1973
12-26-73
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mack Oil Co
Complete Address Box 400 Duncan, OK
Lease Name Baier Well No. 1
Location NW/SE/NW Sec. 23 Twp. 33 Rge. 14 (E) (W) W
County Barber Total Depth 4917
Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Russ Casing Pulling Co Inc
Address Box 1082 Great Bend, KS License No. 623
Operation Completed: Hour 11:00 AM Day 24 Month 12 Year 1973

The above well was plugged as follows:

314 ft 8 5/8 surface cement circulated. 4914 ft 4 1/2 long string
cemented with 100 sacks. Top perf. 4712 ft. Sand to 4700 ft. Pulled
3600 ft 4 1/2. Set 10 ft rock bridge at 320 ft. Fill hole with 5 yds
redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 12/28/73

INV. NO. 8330-W