

15-007 - 10602 - 0020

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
MAY 20 1974  
5-20-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name E.K. Edmiston

Complete Address 405 1st Natl Bldg Wichita, KS

Lease Name Harbaugh D Well No. 1

Location C NW/SE/NE Sec. 22 Twp. 33 Rge. 14 (E) (W) W

County Barber Total Depth 4775

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corp.

Address Box 187 Medicine Lodge, KS License No. 583

Operation Completed: Hour 5:00 PM Day 17 Month 5 Year 1974

The above well was plugged as follows:

266 ft 10 3/4 surface cemented with 200 sacks. 4774 ft 4 1/2 long string  
cemented with 100 sacks. Top perf. 4717 ft. Sand to 4700 ft, 4 sacks  
cement with bailer. Pulled 3500 ft 4 1/2. Lost bailer & 200 ft of line  
in hole. Set 10 ft rock bridge at 200 ft. Fill hole with 5 yds  
redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 5/21/74

INV. NO. 9137-W