

15-007-10339-00-60

Form CP-3
Rev. 6-4-68



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1974
10-29-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Don C. Rider
Complete Address 104 W Lockwood, Medicine Lodge, KS
Lease Name Harbaugh Well No. 1
Location SW/W/2 SE Sec. 22 Twp. 33 Rge. 14 (E) (W) W
County Barber Total Depth 4747
Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Russ Casing Pulling Co Inc
Address Box 1082 Great Bend, KS License No. 623
Operation Completed: Hour 1030 AM Day 22 Month 10 Year 1974

The above well was plugged as follows:
225 ft 13 3/4 surface cemented with 250 sacks. 1029 ft 8 5/8 surface
cemented with 1000 sacks. 4678 ft 5 1/2 long string cemented with 100
sacks. Open hole. Sand to 4600 ft, 5 sacks cement with bailer.
Pulled 4200 ft 5 1/2. Pulled 237 ft 8 5/8. Set 10 ft rock bridge at
140 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10/31/74
INV. NO. 203-W