

B

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 20416 ~~007-2446-0000~~ (of this well)

Operator's Full Name Molz Oil Co.

Complete Address RR 2 Box 54 Kiowa, Ks. 67070

Lease Name Rathgerber Well No. B-1

Location C N/2 SE SW Sec. 6 Twp. 35S Rge. 11 (E) (W) X

County Barber Total Depth 5177

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Corporation

Address 107 W. Fowler, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 4:30 Pm. Day 15 Month 6 Year 1979

The above well was plugged as follows:

325' 10 3/4" casing w/250 sax cement. 4 1/2" casing set at 5176' w/200
sax cement. Preforated at 4796'-Allied mixed & pumped 60 sax common
cement in 4 1/2" casing-Release plug -Pumped plug to 4570'- Shut in
w/1000# pressure.Pull 4150' 4 1/2" casing-Allied mixed & pumped 50sax
hulls-25 sax gel-190 sax 50/50 posmix cement w/3% gel & 3% cc to top
of casing. Shut in w/ 300# pressure.

RECEIVED
STATE CORPORATION COMMISSION
6-18-79
JUN 18 1979

I hereby certify that the above well was plugged as herein stated

INVOICED

DATE 6-18-79
INV. NO. 9855-W

CONSERVATION DIVISION
Signed: [Signature]
Well Plugging Supervisor