

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 23 1973  
2-23-73  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Braden-Deem Inc  
Complete Address 200 E 1st Wichita, KS  
Lease Name Wheat Well No. 2  
Location NW/SW Sec. 27 Twp. 33 Rge. 14 (E) W  
County Barber Total Depth 4779  
Abandoned Oil Well  Gas Well  <sup>AND REC</sup> Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Voth Casing Pulling Co  
Address 715 S A Arkansas City, KS License No. 684  
Operation Completed: Hour 2:00 PM Day 22 Month 2 Year 1973

The above well was plugged as follows:  
378 ft 8 5/8 surface cemented with 275 sacks. 4779 ft 5 1/2 long string  
cemented with 200 sacks. Top perf. 4626 ft. Sand to 4600 ft, 5 sacks  
cement with bailer. Pulled 3550 ft 5 1/2. Set 10 ft rock bridge at  
360 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED  
DATE 2/28/73  
INV. NO. 9045-W