

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

SEP 12 1975
9-12-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Champlin Petroleum Co

Complete Address 6051 N Brooklin Suite 116 Oklahoma City, OK

Lease Name U.B. Harbaugh Unit Well No. 1

Location C S/2 SW/NE Sec. 27 Twp. 33 Rge. 14 (E) (W)

County Barber Total Depth 4716

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Lillard Casing Pulling Co Inc

Address Box 926 Woodward, OK License No. 618

Operation Completed: Hour 5:00 PM Day 10 Month 9 Year 1975

The above well was plugged as follows:

199 ft 13 3/8 surface cemented with 225 sacks. 872 ft 8 5/8 surface
cemented with 125 sacks. 4716 ft 4 1/2 long string cemented with 125
sacks. Top perf. 4669 ft. Pump 35 sacks cement to 4400 ft. Pulled
3148 ft 4 1/2. Pulled 278 ft 8 5/8. Pump 2 sacks hulls, plug, 50 sacks
cement to 190 ft. Mud to 40 ft, plug, 15 sacks cement to surface.

Weld plate on SP.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russell Robertson
Well Plugging Supervisor

DATE 9-15-75

INV. NO. 1912-W