

3021659

TO:

6-15

API NUMBER 15-001-03501-0000

STATE CORPORATION COMMISSION

SE , SEC. 18, T 26 S, R 18 ECONSERVATION DIVISION - PLUGGING SECTION 1450 FEET FROM SOUTH SECTION LINEWICHITA STATE OFFICE BLDG., 130 S. MARKET 479 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BURTISS WELL # 78

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLENOPERATOR LICENSE # 101WELL TOTAL DEPTH APPROX. 800' FEETOPERATOR: STATE OF KANSASPRODUCTION CSG: SIZE FEET NAME AND FEE FUND PLUGGINGSURFACE CASING: SIZE 8" FEET N/AADDRESS ABANDONED OIL WELL ☒ GAS WELL INPUT WELL SWD WELL D/A OTHER WELL AS HEREINAFTER INDICATED PLUGGING CONTRACTOR SPLANE PULLING & ROUSTABOUT SERVICE LICENSE NUMBER 6372ADDRESS P.O. BOX 386, ROUTE 4, CHANUTE, KS 66720COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 15 MONTH: 6 YEAR: 99PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 800' THAT HAD BEEN
CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE THE 4 1/2" CASING AT 500'
AND AT 200' AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND
OUTSIDE THE 4 1/2" CASING.

PLUGGING PROPOSAL RECEIVED BY C.P. TITELPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL ☒ PART NONE OPERATIONS COMPLETED: HOUR: 2:15 PM DAY: 15 MONTH: 6 YEAR: 99

ACTUAL PLUGGING REPORT THE 4 1/2" CASING WAS PERFORATED AT 500' AND AT 200'. 1" PIPE
WAS RAN INTO THE 4 1/2" CASING TO 750'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT
CIRCULATED AT SURFACE FROM BOTH THE 4 1/2" AND 8" ANNULUS. THE 1" PIPE WAS REMOVED.
SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. 156 SACKS OF CEMENT WERE PUMPED
INTO THIS WELL.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas
FORM CP-2/3

RECEIVED
STATE CORPORATION COMMISSION

JUN 25 1999

Control # 19990001-043