

TO:

API NUMBER 15-001-03557-0000

STATE CORPORATION COMMISSION

SE1/4 SEC.18, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

215 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BURTIS WELL # 79

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLENOPERATOR LICENSE # 101WELL TOTAL DEPTH APPROX. 800' FEETOPERATOR: KCC DISTRICT #3PRODUCTION CSG: SIZE FEET NAME AND FEE FUND PLUGGING SURFACE CASING: SIZE 6" FEET ?ADDRESS CHANUTE, KS. 66720ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A OTHER WELL AS HEREINAFTER INDICATED PLUGGING CONTRACTOR SPLANE PULLING & ROUSTABOUT SERVICE, INC. LICENSE NUMBER 6372Address RR4, BOX 386, CHANUTE, KANSAS 66720COMPANY TO PLUG AT: HOUR: 8:00AM DAY: 23 MONTH: 12 YEAR: 98PLUGGING PROPOSAL RECEIVED FROM Clayton P. Titel(COMPANY NAME) Kansas Corporation Commission (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN AT
T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF
CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TitelPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE OPERATIONS COMPLETED: HOUR: DAY: 23 MONTH: 12 YEAR: 98

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE 2" CASING TO 750'. CEMENT WAS PUMPED
INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. The 1" PIPE WAS
REMOVED. 1" PIPE WAS RAN INTO THE 2" & 6" ANNULUS TO 450'. CEMENT WAS PUMPED INTO THE 1"
PIPE UNTIL CEMENT CIRCULATED FROM THE 6" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED
SETTLAGE & DISPLACEMENT WERE FILLED FROM THE SURFACE. 206 SACKS OF CEMENT WERE PUMPED

REMARKS: INTO WELL.(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXX XXX)OBSERVE THIS PLUGGING.

SIGNED Clayton P. Titel
(TECHNICIAN) FORM CP-2/3

Control # 19990001-044