

3021618

TO:

API NUMBER 15-001-03566-0000

STATE CORPORATION COMMISSION

4-26 SE, SEC. 18, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION 1636 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 215 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BURTISS WELL # 39

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE # 101

WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS

PRODUCTION CSG: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 10" FEET

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SPLANE PULLING & ROUSTABOUT SERVICE LICENSE NUMBER 6372

ADDRESS P.O. BOX 386, ROUTE 4, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 11:10AM DAY: 26 MONTH: 4 YEAR: 99

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 10" SURFACE CASING. THE WELL MAY HAVE BEEN PLUGGED IN THE PAST. THE PLUGGING PROPOSAL WAS TO DRILL THE WELL OUT TO 500' AND TO CIRCULATE THE WELL FULL OF CEMENT FROM 500' TO SURFACE.

 PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:00 PM DAY: 26 MONTH: 4 YEAR: 99

ACTUAL PLUGGING REPORT WOOD AND CAVINGS WERE DRILLED FROM THE WELL TO 482'. AT 482' IRON WAS ENCOUNTERED. NO CEMENT WAS FOUND. 1" PIPE WAS RAN INTO THE WELL TO 482'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGES AND DISPLACEMENT WERE FILLED FROM SURFACE. 225 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3

MAY 17 1999

CONSERVATION DIVISION

Wichita, Kansas

Control # 19990001-055