

3021607

TO:

API NUMBER 15-001-03595-0000

STATE CORPORATION COMMISSION

4-7

SE, SEC. 18, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION 2471 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2160 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BURTISS WELL # 63

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE # 101

WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS

PRODUCTION CSG: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 10" FEET

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SPLANE PULLING & ROUSTABOUT SERVICES LICENSE NUMBER 6372

ADDRESS P.O. BOX 386, ROUTE 4, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 9:30AM DAY: 7 MONTH: 4 YEAR: 99

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: VISIBLE AT SURFACE ON THIS WELL WAS 10" SURFACE CASING ONLY. WOOD WAS

ENCOUNTERED IN THE WELL AT APPROXIMATELY 20'. THE PLUGGING PROPOSAL WAS TO DRILL THE

WELL OUT TO 500' AND CIRCULATE THE WELL FULL OF CEMENT FROM 500' TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:30 DAY: 7 MONTH: 4 YEAR: 99

ACTUAL PLUGGING REPORT THE WELL WAS DRILLED OUT TO 523'. IT WAS DISCOVERED THAT A

WOODEN PLUG WAS FLOATING BELOW THE DRILL BIT. IT WAS DECIDED TO PLUG THROUGH THE DRILL

PIPE. THE DRILL PIPE WAS AT 523'. CEMENT WAS PUMPED INTO THE DRILL PIPE UNTIL CEMENT

CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE DRILL PIPE WAS REMOVED. SETTLAGE

AND DISPLACEMENT WERE FILLED FROM SURFACE. 237 SACKS OF CEMENT WERE PUMPED INTO THIS

WELL.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

RECEIVED

I (DID/XXXXXXX) OBSERVE THIS PLUGGING

SIGNED

Clayton P. Titel

(TECHNICIAN)

FORM CP-2/3

Control # 19990001-076 APR 19 1999

CONSERVATION DIVISION
Wichita, Kansas